



Haralson County
Board of Commissioners

Ronald J. Ridley
Chairman/C.E.O.

Please see the attached Invitations to Bid for Haralson County.

All roads should be bid as one package only.

A bid bond will be required.

As noted on the invitations, bids are due back no later than 9/30/20 at 4:00pm.

As always, we welcome any recommendations or questions you may have. In the event that I can't be contacted, please contact our Director, Terry Edwards, at terryedwards@haralsoncountyga.gov or 770-646-3278.

**Haralson County Public Works Department
INVITATION TO BID**

Resurfacing & Striping – Aldridge Lane

Haralson County is accepting proposals for resurfacing & striping .37miles of Aldridge Lane from Susie Pope Road to Hwy. 100 North. The road is to be resurfaced with & Recycled 9.5MM Type 2 including Bitum & H Lime (165///SY). No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

Road Name: Aldridge Lane
Segment: Susie Pope to Hwy. 100 North **Width:** 20' **Length in Miles:** .37

Sealed proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Aldridge Lane".

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

Quantities for Aldridge Lane Resurfacing
From Susie Pope to Hwy. 100 North
Resurfacing Length - .37 miles Width - 20'

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|-------------------|---|-------|----------|----------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | Recycled 9.5MM Type 2 including Bitum Tackcoat & H Lime (165#/SY) | Tons | 357 | | |
| 3 | Milling Variable for the tie ins | SY | 0 | | |
| 4 | Single white stripe 5" painted | LM | .74 | | |
| 5 | Double yellow stripe 5" painted | LM | .37 | | |
| BID TOTAL: | | | | | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase.
 Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.

Note 5: 20' paved apron should be installed at any & all entrances to intersecting gravel roads.

**Haralson County Public Works Department
INVITATION TO BID**

NEW PAVING – Eady Drive

Haralson County is accepting proposals for New Paving of .35miles of Eady Drive from Bushmill Road to dead end. The road is to be paved with Recycled 12.5MM & 11 Lime totaling 220#/SY. No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

| | | | |
|-------------------|----------------------------------|-------------------|-----------------------------|
| Road Name: | Eady Drive | | |
| Segment: | Bushmill Road to dead end | Width: 20' | Length in Miles: .35 |

Sealed proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Eady Drive".

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

Quantities for Eady Drive New Paving
From Bushmill Road to dead end
Resurfacing Length - .35 miles Width -20'ft.

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|-------------------|--|-------|----------|----------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | Recycled 12.5MM & H Lime (220#/SY) | Tons | 464 | | |
| 3 | Milling Variable for the tie ins | SY | 0 | | |
| 4 | Single white stripe 5" painted | LM | .7 | | |
| 5 | Double yellow stripe 5" painted | LM | .35 | | |
| BID TOTAL: | | | | | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase. Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.

Note 5: 20' paved apron should be installed at any & all entrances to intersecting gravel roads.

**Haralson County Public Works Department
INVITATION TO BID**

Resurfacing & Striping – Jacksonville Road

Haralson County is accepting proposals for resurfacing & striping. 5.57miles of Jacksonville Rd. from Hwy. 100 N.to Alabama State line. The road is to be resurfaced with Recycled Leveling including Bitum Tackcoat & H Lime (85#/SY) & Recycled 9.5MM Type I including Bitum & H Lime (135#/SY), totaling 220#/SY. No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

| | | | |
|-------------------|---------------------------------------|-------------------|------------------------------|
| Road Name: | Jacksonville Road | | |
| Segment: | Hwy. 100 to Alabama State line | Width: 22' | Length in Miles: 5.57 |

Sealed proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Jacksonville Road".

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

**Quantities for Jacksonville Road Resurfacing
From Highway 100 to Alabama state line
Resurfacing Length – 5.57 miles Width – 22'**

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|-------------------|---|-------|----------|----------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | Recycled Leveling including Bitum Tackcoat & H Lime (85#/SY) | Tons | 3,055 | | |
| 3 | Recycled 9.5MM Type I including Bitum Tackcoat & H Lime (135#/SY) | Tons | 4,854 | | |
| 4 | Milling Variable for the tie ins | SY | 0 | | |
| 5 | Single white stripe 5" painted | LM | 11.14 | | |
| 6 | Double yellow stripe 5" painted | LM | 5.57 | | |
| BID TOTAL: | | | | | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase.
Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.

Note 5: 20' paved apron should be installed at any & all entrances to intersecting gravel roads.

Note 6: Safety barrels are required by Contractor until asphalt has cured to the point of Haralson County completing backfill

**Haralson County Public Works Department
INVITATION TO BID**

Resurfacing & Striping – Old Hamilton Mill

Haralson County is accepting proposals for resurfacing & striping .73 miles of Old Hamilton Mill Road from Shedd Road to dead end. The road is to be resurfaced with Recycled Leveling including Bitum Tackcoat & H Lime (85#/SY) & Recycled 9.5MM Type I including Bitum & H Lime (135#/SY), totaling 220#/SY. No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

Road Name: Old Hamilton Mill
Segment: Shedd Road to dead end **Width:** 20' **Length in Miles:** .73

Scaled proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Old Hamilton Mill".

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

Quantities for Old Hamilton Mill Road Resurfacing
From Shedd Road_to dead end
Resurfacing Length -- .73 miles Width --20'

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|-------------------|---|-------|----------|----------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | Recycled Leveling including Bitum Tackcoat & H Lime (85#/SY) | Tons | 365 | | |
| 3 | Recycled 9.5MM Type 1 including Bitum Tackcoat & H Lime (135#/SY) | Tons | 580 | | |
| 4 | Milling Variable for the tie ins | SY | 0 | | |
| 5 | Single white stripe 5" painted | LM | 1.46 | | |
| 6 | Double yellow stripe 5" painted | LM | .73 | | |
| BID TOTAL: | | | | | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase.
Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.

**Haralson County Public Works Department
INVITATION TO BID**

Resurfacing & Striping – Old Hwy. 100

Haralson County is accepting proposals for resurfacing & striping, 6.23miles of Old Hwy. 100 from Tallapoosa City Limits to Carroll County line. The road is to be resurfaced with Recycled Leveling including Bitum Tackcoat & H Lime (85//SY) & Recycled 9.5MM Type I including Bitum & H Lime (135//SY), totaling 220//SY. No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

Road Name: Old Hwy. 100
Segment: Tallapoosa city Limits to Carroll Co. Line **Width:** 21' **Length in Miles:** 6.23

Sealed proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Old Hwy. 100".

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

**Quantities for Old Hwy. 100 Resurfacing
From Tallapoosa City Limits to Carroll County line
Resurfacing Length – 6.23 miles Width –21'**

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|-------------------|---|-------|----------|----------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | Recycled Leveling including Bitum Tackcoat & H Lime (85#/SY) | Tons | 3,265 | | |
| 3 | Recycled 9.5MM Type 1 including Bitum Tackcoat & H Lime (135#/SY) | Tons | 5,185 | | |
| 4 | Milling Variable for the tie ins | SY | 350 | | |
| 5 | Single white stripe 5" painted | LM | 12.46 | | |
| 6 | Double yellow stripe 5" painted | LM | 6.23 | | |
| BID TOTAL: | | | | | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase.
Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.

Note 5: 20' paved apron should be installed at any & all entrances to intersecting gravel roads.

Note 6: Safety barrels are required by Contractor until asphalt has cured to the point of Haralson County completing backfill

**Haralson County Public Works Department
INVITATION TO BID**

Resurfacing & Striping – Payne Milling Drive

Haralson County is accepting proposals for resurfacing & striping .24 miles of Payne Milling Drive from Hwy. 100 South to Payne Milling Road. The road is to be resurfaced with recycled 9.5MM Type 1 including Bitum & H Lime (165#/SY). No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

Road Name: Payne Milling Drive
Segment: Hwy. 100 South to Payne Milling Road **Width:** 12' **Length in Miles:** .24

Sealed proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Payne Milling Drive".

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

**Quantities for Payne Milling Drive Resurfacing
From Hwy. 100 South to Payne Milling Road
Resurfacing Length -- .24 miles Width -- 12',**

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|------|---|-------|-------------------|----------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | 9.5MM Type 1 including Bitum Tackcoat & 11 Lime (165#/SY) | Tons | 140 | | |
| 3 | Milling Variable for the tie ins | SY | 0 | | |
| 4 | Single white stripe 5" painted | LM | 0 | | |
| 5 | Double yellow stripe 5" painted | LM | 0 | | |
| | | | BID TOTAL: | | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase.
Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.

Word:bidproposal,PayneMillingDrive

**Haralson County Public Works Department
INVITATION TO BID**

Resurfacing & Striping – Payne Milling Road

Haralson County is accepting proposals for resurfacing & striping .72 miles of Payne Milling Road from Hwy. 100 to Old Hwy. 100. The road is to be resurfaced with Recycled Leveling including Bitum Tackcoat & H Lime (80#/SY) & Recycled 9.5MM Type I including Bitum & H Lime (135#/SY) totaling (215#/SY). No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

Road Name: Payne Milling Road
Segment: Hwy. 100 to Old Hwy. 100 **Width:** 18' **Length in Miles:** .72

Sealed proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Payne Milling Road.

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

| |
|--|
| <p>Quantities for Payne Milling Road Resurfacing From Hwy. 100 to Old Hwy. 100 Resurfacing Length - .72 miles Width -18'</p> |
|--|

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|-------------------|---|-------|----------|----------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | Recycled Leveling including Bitum Tackcoat & H Lime (80#/SY) | Tons | 304 | | |
| 3 | Recycled 9.5MM Type 1 including Bitum Tackcoat & H Lime (135#/SY) | Tons | 513 | | |
| 4 | Milling Variable for the tie ins | SY | 200 | | |
| 5 | Single white stripe 5" painted | LM | 1.54 | | |
| 6 | Double yellow stripe 5" painted | LM | .72 | | |
| BID TOTAL: | | | | | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase.
 Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.

**Haralson County Public Works Department
INVITATION TO BID**

NEW PAVING – Pope Road

Haralson County is accepting proposals for NEW PAVING & striping .45miles of Pope Road from Buchanan Bypass to dead end. The road is to be paved with Recycled 12.5MM & H Lime (220#/SY). No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

Road Name: Pope Road
Segment: Buchanan Bypass to dead end **Width:** 20' **Length in Miles:** .45

Sealed proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Pope Road".

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

| |
|--|
| Quantities for Pope Road NEW PAVING From Buchanan Bypass to dead end Length - .45miles Width - 20' |
|--|

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|------|--|-------|----------|-------------------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | Recycled 12.5MM & H Lime (220#/SY) | Tons | 586 | | |
| 3 | Milling Variable for the tie ins | SY | 0 | | |
| 4 | Single white stripe 5" painted | LM | .9 | | |
| 5 | Double yellow stripe 5" painted | LM | .45 | | |
| | | | | BID TOTAL: | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase.
Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.

**Haralson County Public Works Department
INVITATION TO BID**

Resurfacing & Striping – Poplar Springs Road

Haralson County is accepting proposals for resurfacing & striping 3.83 miles of Poplar Springs road from Jacksonville Road to Susie Pope Road. The road is to be resurfaced with Recycled Leveling including Bitum Tackcoat & H Lime (80#/SY) & Recycled 9.5MM Type 1 including Bitum & H Lime (135#/SY) totaling 215#/SY. No resurfacing shall be done unless the temperature is at least 45 degrees & rising; and all work is to be done to DOT specifications. Below is an overview of the roadwork in question:

Road Name: Poplar Springs Road
Segment: Jacksonville Road to Susie Pope Road **Width:** 18' **Length in Miles:** 3.83

Sealed proposals on the enclosed forms will be received at the Haralson County Public Works Department office, 1801 Macedonia Church Road, Buchanan, GA 30113, until 9/30/20 @ 4:00pm. Envelopes must be marked "Haralson County Road Project Poplar Springs Road".

The County reserves the right to do all, some, or none of the aforementioned. The County will bear the cost of any utility facility removal & relocations necessary in connection with the construction of this project. County will be responsible for backfill to edge of pavement upon completion of resurfacing. County will be responsible for final grassing of project. The contractor will be responsible for signage & traffic control during project & temporary pavement markings upon completion of resurfacing. Please contact Terry Edwards at (770) 646-3278 with any questions.

The County will pay the contractor for work completed at the stated unit prices (less retainage) as described herein.

The County will retain 10% of said contract payments until the satisfactory completion of all work & the final acceptance of said work by all parties. Upon such final acceptance, the County will remit to the contractor all amounts remaining due under the terms of the contract.

Time is of the essence in this contract & all work must be completed within 90 days of the notice to proceed. The County will assess a \$200.00 per day penalty after the 90 days have expired. Notice to Proceed will be issued & awarded & signed contract.

The completed bid form & all material included in this Invitation to Bid package shall be made part of any contract with the successful bidder. All bidders must provide documentation demonstrating their compliance with E-Verify/SAVE Programs (as these mandates are applicable to this bid).

HARALSON COUNTY PUBLIC WORKS

| |
|---|
| <p>Quantities for Poplar Springs Road From Jacksonville Road to Susie Pope Road Resurfacing Length – 3.83 miles Width – 18'</p> |
|---|

| No.: | Item: | Unit: | Est.Qty: | Unit \$: | Total \$: |
|-------------------|---|-------|----------|----------|-----------|
| 1 | Traffic Control: IN (In accordance with Current MUTCD) | | 1 | | |
| 2 | Recycled Leveling including Bitum Tackcoat & H Lime (80#/SY) | Tons | 1,580 | | |
| 3 | Recycled 9.5MM Type 1 including Bitum Tackcoat & H Lime (135#/SY) | Tons | 2,667 | | |
| 4 | Milling Variable for the tie ins | SY | 350 | | |
| 5 | Single white stripe 5" painted | LM | 7.66 | | |
| 6 | Double yellow stripe 5" painted | LM | 3.83 | | |
| BID TOTAL: | | | | | |

Note 1: Contractor responsible for all signage & safety measures until asphalt cured enough for Haralson County to backfill paving.

Note 2: Temporary signage will be acceptable during construction phase.
 Permanent "Low Soft Shoulder" signs are required.

Note 3: Temporary striping in accordance with Georgia DOT specification final striping installed 30 days later.

Note 4: Widen spreader gate 2 foot at driveways.